

# **ANDOVER CLUB** 3450 & 3550 TODDS ROAD CLUBHOUSE

DEVELOPER: ANDERSON ACQUISITIONS, LLC 1720 SHARKEY WAY LEXINGTON, KENTUCKY 40511

STANDARDS OF CONSTRUCTION L.F.U.C.G. STANDARDS, L.F.U.C.G. SUBDIVISION REGULATIONS AND KENTUCKY DEPARTMENT OF HIGHWAYS SPECIFICATIONS, ALL LATEST EDITIONS, SHALL APPLY TO THE WORK DESCRIBED WITHIN THESE PLAN DOCUMENTS UNLESS SPECIFICALLY DIRECTED BY NOTE OTHERWISE.

	SHEET INDEX
5C	PRELIMINARY SUBDIVISION PLAN GENERAL NOTES DEMOLITION PLAN DEMOLITION AND EROSION CONTROL PLAN SITE LAYOUT PLAN STRIPING PLAN GRADING AND EROSION CONTROL PLAN WETLANDS PLANTING SCHEDULE STORM AND SANITARY SEWER PLAN STREET PROFILES STORM SEWER PROFILES BEST MANAGEMENT PRACTICES PLAN BEST MANAGEMENT PRACTICES DETAILS STORM SEWER CALCULATIONS
	BAPartners, PLC   Description   Description   Civil Engineers - Land Surveyors - Landscape architects   Still Wall Street   Discription (659) 296-9887





#### GENERAL CONDITIONS

PRIOR TO THE MOBILIZATION OF EQUIPMENT, A PRECONSTRUCTION/PRE-EROSION CONTROL CONFERENCE SHALL BE HELD ON SITE ATTENDED BY THE CONTRACTOR, THE ENGINEER, THE OWNER AND THE LFUCG.

WITHIN IO DAY'S FOLLOWING THE PRECONSTRUCTION CONFERENCE, A PROJECT SCHEDULE SHALL BE SUBMITTED BY THE CONTRACTOR TO THE ENGINEER.

PRIOR TO MOBILIZATION, THE CONTRACTOR SHALL ERECT A PROJECT SIGN INDICATING THE CONTRACTOR, THE ENGINEER AND THE OWNER. THE SIGN FORMAT SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO ERECTION.

UNLESS OTHERWISE NOTED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND LICENSES.

DURING THE PROGRESS OF THE WORK, THE CONTRACTOR SHALL KEEP THE PREMISES FREE FROM ACCUMULATIONS OF WASTE MATERIALS, RUBBISH AND OTHER DEBRIS RESULTING FROM THE WORK.

AT THE COMPLETION OF THE PROJECT, THE CONTRACTOR SHALL REMOVE ALL WASTE MATERIAL, RUBBISH AND DEBRIS FROM AND ABOUT THE PREMISES AS WELL AS ALL TOOLS, APPLIANCES, CONSTRUCTION EQUIPMENT AND MACHINERY AND SURPLUS MATERIALS, AND SHALL LEAVE THE SITE CLEAN AND READY FOR OCCUPANCY BY THE OWNER.

THE CONTRACTOR SHALL CONSTRUCT AND MAINTAIN, IN A SANITARY CONDITION, SANITARY FACILITIES FOR HIS EMPLOYEES AND SUBCONTRACTORS. AT THE COMPLETION OF THE WORK, THE CONTRACTOR SHALL PROPERLY DISPOSE OF THESE SANITARY FACILITIES.

#### <u>SUBMITTALS</u>

THE CONTRACTOR SHALL PROVIDE MATERIAL CERTIFICATIONS FOR ALL MATERIALS USED ON THE PROJECT INCLUDING STORM SEWERS, SANITARY SEWERS, PRECAST STRUCTURES, DENSE GRADED AGGREGATE, BITUMINOUS PAVEMENT AND UNREINFORCED CONCRETE.

THE CONTRACTOR SHALL PROVIDE SHOP DRAWINGS FOR MATERIALS USED ON THE PROJECT. SIX COPIES OF THE SHOP DRAWINGS SHALL BE FORWARDED TO THE ENGINEER FOR APPROVAL PRIOR TO ORDERING.

#### <u>STANDARDS OF CONSTRUCTION</u>

LFUCG STANDARDS, LFUCG SUBDIVISION REGULATIONS AND KENTUCKY DEPARTMENT OF HIGHWAY'S SPECIFICATIONS, ALL LATEST EDITIONS, SHALL APPLY TO THE WORK DESCRIBED WITHIN THESE PLAN DOCUMENTS UNLESS SPECIFICALLY DIRECTED BY NOTE OTHERWISE.

#### UTILITY LOCATIONS/BEFORE YOU DIG

THE CONTRACTOR IS ADVISED THAT UTILITY LOCATIONS SHOWN WITHIN THESE PLAN DOCUMENTS ARE APPROXIMATE AND NEED TO BE VERIFIED PRIOR TO BEGINNING WORK. THE ULTIMATE RESPONSIBILITY FOR UNDERGROUND UTILITY LOCATIONS IS THE CONTRACTOR'S.

THE CONTRACTOR IS ADVISED THAT HE SHOULD CALL I-800-152-600T, TOLL FREE, A MINIMUM OF 48 HOURS PRIOR TO EXCAVATION FOR INFORMATION ON THE LOCATION OF EXISTING UNDERGROUND UTILITIES.

THE CONTRACTOR SHALL USE ALL POSSIBLE CARE IN EXCAVATING ON THE PROJECT TO AVOID DAMAGE TO EXISTING UTILITIES, WHETHER OR NOT THE UTILITIES ARE OR ARE NOT SHOWN ON THE PLANS. EXISTING UTILITIES AND LOCATIONS OF EXISTING UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE ONLY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION AND RESTORATION OF EXISTING UTILITY PROPERTY.

#### CONSTRUCTION LAYOUT

CONSTRUCTION STAKING TO BE PROVIDED BY THE OWNER.

#### <u>TRENCH ROCK EXCAVATION</u>

THE PAY LIMITS FOR TRENCH ROCK EXCAVATION ARE AS FOLLOWS: TRENCH ROCK EXCAVATION SHALL BE MEASURED IN CUBIC YARDS BASED ON A TRENCH WIDTH OF 3.0 FEET FOR 4, 6 OR 8 INCH PIPE AND THE OUTSIDE DIAMETER PLUS 2 FEET FOR LARGER PIPE. THE DEPTH OF THE TRENCH ROCK SHALL BE AN AVERAGE OF 50 FOOT STATIONS AS MEASURED IN THE FIELD TO A DEPTH OF 6 INCHES BELOW THE PIPE GRADE. ADDITIONAL STONE BACKFILL IN ROCK EXCAVATIONS WILL NOT BE MEASURED FOR PAYMENT.

#### <u>ROCK EXCAVATION</u>

SHOULD ROCK REMOVAL BE PERFORMED BY BLASTING, THE CONTRACTOR SHALL PERFORM ALL OPERATIONS IN STRICT CONFORMANCE WITH ALL APPLICABLE LAWS.

#### <u>CLEARING, GRUBBING AND REMOVAL</u>

PRIOR TO COMMENCEMENT OF CLEARING, GRUBBING AND REMOVALS, ANY AREAS DESIGNATED ON THE PLANS AS "TREE PRESERVATION AREAS" OR "DO NOT DISTURB AREAS" SHALL BE DESIGNATED WITH ORANGE SAFETY FENCE OR SECURITY TAPE AS DIRECTED BY THE ENGINEER.

THE ENTIRE AREA WITHIN THE CONSTRUCTION LIMITS SHALL BE CLEARED OF ALL WEEDS, BRUSH, BRIERS, TREES, STUMPS, AND OTHER PROTRUDING OBSTRUCTIONS NOT DESIGNATED TO REMAIN, EXCEPT WITHIN AREAS THE ENGINEER MAY DESIGNATE TO REMAIN UNDISTURBED.

ALL BUGHEG, TREEG, ROOTG AND STUMPS WITHIN THE CONSTRUCTION LIMITG SHALL BE GRUBBED EXCEPT UNDISTURBED STUMPS, ROOTG AND NONPERIGHABLE GOLID OBJECTG WHICH WILL BE A MINIMUM OF THREE FEET BELOW THE SUBGRADE OR EMBANKMENT FOUNDATION.

ALL TOPGOIL AND/OR UNGUITABLE MATERIAL SHALL BE STRIPPED AND STOCKPILED DURING THE CLEARING AND GRUBBING OPERATIONS.

ALL MATERIALS RESULTING FROM THE CLEARING AND GRUBBING OPERATIONS SHALL BE DISPOSED OF BY THE CONTRACTOR AT THE DIRECTION OF THE OWNER/DEVELOPER. THE MATERIAL SHALL NOT BE BURIED ON SITE WITHIN LOTS, RIGHT-OF-WAYS, OR DESIGNATED GREENWAYS. BURNING PITS SHALL BE LOCATED AS DIRECTED BY THE ENGINEER AND APPROVED BY THE FIRE MARSHALL.

## <u>GEOTECHNICAL NOTES</u>

ALL TOPSOIL AND ORGANIC MATERIAL SHALL BE REMOVED WITHIN THE LIMITS OF ANY PROPOSED CONSTRUCTION ACTIVITIES. PROOF ROLL THE EXPOSED SURFACE OF ANY ANTICIPATED FILL AREA AND OR PAVEMENT AREA TO DETERMINE IF ANY UNSTABLE SOIL CONDITIONS EXIST.

EQUIPMENT USED FOR PROOF ROLLING SHALL BE A LOADED PNEUMATIC TIRED VEHICLE SUCH AS A DUAL AXLE DUMP TRUCK WITH A GROSS WEIGHT OF 16 TO 20 TONS.

IF ANY UNSTABLE AREAS ARE EXPOSED BY PROOF ROLLING, THOSE AREAS SHALL BE UNDERCUT AND REPLACED WITH PROPERLY COMPACTED MATERIAL.

SOILS PLACED AS FILL OR BACKFILL WITHIN THE PROPOSED SITE SHALL BE COMPACTED TO 95 PERCENT OF THE MAXIMUM DRY DENSITY AT A MOISTURE CONTENT WITHIN -4 TO +2 PERCENT OF OPTIMUM.

A SHEEPSFOOT ROLLER SHALL BE USED TO COMPACT COHESIVE FILL MATERIAL AND A SMOOTH DRUM VIBRATORY ROLLER USED FOR GRANULAR SOILS. A HAND WHACKER OR VIBRATORY PLATE SHALL BE USED TO COMPACT BACKFILL WITHIN SEWER AND UTILITY TRENCHES.

SHOT ROCK OR MECHANICALLY EXCAVATED ROCK MAY BE USED FOR FILL MATERIAL AS LONG AS THE LARGEST DIMENSION IN ANY DIRECTION OF THE ROCK FRAGMENT DOES NOT EXCEED 6 INCHES. LIFT THICKNESSES SHALL NOT EXCEED 12 INCHES.

EVALUATION OF ROCK FILL PLACEMENT AND THE INTEGRITY OF THE ROCK FILL SHALL BE DETERMINED BY VISUAL INSPECTION OF THE PLACEMENT PROCEDURES BY A QUALIFIED TECHNICIAN WORKING UNDER THE SUPERVISION OF A PROFESSIONAL ENGINEER.

THE USE OF A SOIL/SHOT ROCK MIXTURE WITH MORE THAN 20 PERCENT SOIL FOR FILL CONSTRUCTION SHALL BE LIMITED TO NONSTRUCTURAL AREAS OF THE SITE.

SOIL USED FOR STRUCTURAL FILL SHALL BE PLACED IN LAYERS NO GREATER THAN 10 INCHES IN LOOSE THICKNESS AND COMPACTED TO THE LIMITS PREVIOUSLY MENTIONED.

IN AREAS WHERE THE DENSITY IS ACHIEVED THROUGH THE USE OF HAND OPERATED EQUIPMENT, LOOSE LIFT THICKNESS SHALL NOT EXCEED 5 INCHES.

TESTS FOR THE DEGREE OF COMPACTION FOR SOIL SHALL BE MADE ON EACH LAYER BEFORE PLACEMENT OF THE NEXT LAYER.

ALL TEGTING OF EMBANKMENT OR BACKFILL SHALL BE PROVIDED BY THE OWNER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH THE GEOTECHNICAL FIRM TO INSURE THAT ALL EMBANKMENT OR BACKFILL IS TESTED AND MEETS THE REQUIREMENTS OF THESE STANDARDS AND SPECIFICATIONS.

#### EXCAVATION

EXCAVATION SHALL INCLUDE THE REMOVAL AND DISPOSAL OF MISCELLANEOUS STRUCTURES REMOVED FROM WITHIN THE CONSTRUCTION LIMITS SUCH AS, BUT NOT LIMITED TO, ALL TYPES OF PAVEMENT AND PAVEMENT BASES, WHETHER RIGID OR FLEXIBLE, SIDEWALK, CURBS AND GUTTERS, CONDUITS THAT HAVE NO SALVAGE VALUE, SUCH AS DRAINAGE PIPES, SANITARY SEWER PIPE, WATERLINES, AND OTHER UNSERVICEABLE UTILITY LINES. THE PLANS MAY, OR MAY NOT, INDICATE THE EXACT LOCATIONS OF THE VARIOUS TYPES AND QUANTITIES OF THESE MISCELLANEOUS ITEMS TO BE REMOVED AND DISPOSED OF. HOWEVER, IT IS THE INTENT OF THESE SPECIFICATIONS THAT THE REMOVAL OF ANY SUCH ITEMS THAT FALL WITHIN THE LIMITS OF CONSTRUCTION SHALL BE CONSIDERED UNCLASSIFIED.

EXCEPT AS OTHERWISE SPECIFICALLY STATED, EXCAVATION SHALL INCLUDE INLET AND OUTLET DITCHES, REGARDLESS OF THE CLASSIFICATION OF THE MATERIAL ENCOUNTERED.

WITHOUT REGARD TO THE MATERIALS ENCOUNTERED, ALL EXCAVATION SHALL BE UNCLASSIFIED. IT SHALL BE DISTINCTLY UNDERSTOOD THAT ANY REFERENCE TO ROCK, EARTH OR ANY OTHER MATERIAL ON THE PLANS OR CROSS SECTIONS, WHETHER IN NUMBERS, WORDS, LETTERS, OR LINES IS SOLELY FOR INFORMATION AND SHALL NOT BE TAKEN AS AN INDICATION OF CLASSIFIED EXCAVATION OR THE QUANTITY OF ROCK, EARTH OR OTHER MATERIAL INVOLVED.

THE CONTRACTOR SHALL DRAW HIS OWN CONCLUSIONS AS TO THE CONDITIONS TO BE ENCOUNTERED. THE OWNER OR THE ENGINEER DOES NOT GIVE ANY GUARANTEE AS TO THE ACCURACY OF THE DATA AND NO CLAIM WILL BE CONSIDERED FOR ADDITIONAL COMPENSATION WHEN THE MATERIALS ENCOUNTERED ARE NOT IN ACCORD WITH THE CLASSIFICATION SHOWN.

ALL SUITABLE MATERIAL REMOVED FROM THE EXCAVATION SHALL BE USED, IN SO FAR AS PRACTICAL, IN THE FORMATION OF EMBANKMENTS, SUBGRADE, SHOULDERS, BACKFILL FOR STRUCTURES, OR FOR OTHER PURPOSES SHOWN ON THE PLANS OR AS DIRECTED.

NO EXCAVATED MATERIAL SHALL BE WASTED WITHOUT PERMISSION. EXCAVATED MATERIAL IN EXCESS OF THAT REQUIRED FOR NORMAL EMBANKMENT CONSTRUCTION SHALL NOT BE WASTED WITHIN THE CONSTRUCTION LIMITS, EXCEPT WHEN SPECIFICALLY DIRECTED OR APPROVED.

#### <u>SUBGRADE</u>

THE SUBGRADE SHALL BE COMPACTED, AS NEARLY AS PRACTICAL, TO A UNIFORM DENSITY THROUGHOUT. EXCEPT WHERE OTHERWISE PROVIDED, THE COMPACTION AND MOISTURE CONTROL REQUIREMENTS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF EMBANKMENT CONSTRUCTION. SHOULD THE SUBGRADE SUBSEQUENTLY LOSE IT'S DENSITY DUE TO EXPOSURE TO SEVERE WEATHER CONDITIONS, AFTER HAVING BEEN PREVIOUSLY COMPACTED TO THE REQUIRED DENSITY DURING THE CONSTRUCTION OF THE GRADE, IT SHALL BE RECOMPACTED TO THE REQUIRED DENSITY.

THE SUBGRADE SHALL BE INSPECTED AND TESTED FOR STABILITY BY PROOFROLLING WITH A LOADED TRUCK WEIGHING 3T TONS GROSS WEIGHT. THE TESTING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE PERFORMED UNDER THE DIRECTION OF THE ENGINEER.

AREAS OF YIELDING OR UNSTABLE MATERIAL SHALL BE EXCAVATED AND BACKFILLED WITH APPROVED MATERIALS AS DIRECTED. WHEN THE MATERIAL IN PLACE DOES NOT CONTAIN SUFFICIENT MOISTURE, OR IS TOO WET TO OBTAIN PROPER COMPACTION, THE MOISTURE CONTENT SHALL BE INCREASED OR REDUCED AS DIRECTED, AND THE MATERIAL COMPACTED. SCARIFYING OF THE SUBGRADE MAY BE REQUIRED.

PROVIDE 6" FLEXIBLE PERFORATED PIPE FOR SUBGRADE DRAINAGE 100 FEET EACH WAY FROM SAG BASING AND 100 FEET UPHILL OF BASING ON GRADE, AG SHOWN PER LEXINGTON-FAYETTE URBAN GOVERNMENT STANDARDG SHALL ALGO BE PROVIDED WHERE ROCK IS WITHIN 12" TO 24" OF THE SUBGRADE.

#### <u>SANITARY SEWERS</u>

UNLESS OTHERWISE NOTED, ALL PVC SANITARY SEWERS SHALL BE SDR 35 AND ALL DUCTILE IRON SANITARY SEWERS SHALL BE CLASS 350.

UNLESS OTHERWISE NOTED, ALL SANITARY SEWER LATERALS SHALL BE 6". ALL LATERALS CROSSING PROPERTY LINES SHALL BE CONSTRUCTED WITH A TWO-WAY CLEAN-OUT AS DESIGNATED ON THE PLANS. ALL LATERALS FROM THE MAIN TO THE PROPERTY LINE OR EASEMENT SHALL BE THE SAME MATERIAL AS THE MAIN.

ALL SANITARY SEWER LATERALS SHALL BE CONSTRUCTED A MINIMUM OF 5' FROM THE MAIN SEWER LINE AND CONSTRUCTED TO WITHIN 6'OF THE FINISHED GRADE.

ALL SANITARY LATERALS SHALL BE LOCATED WITH A 6'LENGTH OF NO.5 REBAR AT THE END OF THE LATERAL.

ALL BURIED DUCTILE IRON PIPE SHALL HAVE MANUFACTURER'S OUTSIDE COAL TAR OR ASPHALTIC BASE COATING AND SHALL BE COATED WITH PROTECTO 401 CERAMIC EPOXY IN ACCORDANCE WITH THE LEXINGTON-FAYETTE URBAN COUNTY GOVERNMENT SANITARY SEWER SPECIFICATIONS.

ALL SANITARY AND STORM SEWER MANHOLES SHALL BE MARKED WITH A SAFETY FENCE IN A "V" SHAPE.

ALL TAPS INTO MANHOLES MUST BE FACTORY INSTALLED WITH (A-LOCK OR EQUAL) WATER STOPS. NO MORE THAN 3 TAPS SHALL BE ALLOWED PER MANHOLE. NO MORE THAN A 2 FOOT DROP SHALL BE ALLOWED FROM TAP TO THE INVERT.

ALL PVC SANITARY SEWERS SHALL BE SUBJECTED TO A LOW PRESSURE AIR TEST AND MANDREL INSPECTION. THE MANDREL INSPECTION SHALL BE PERFORMED NO SOONER THAN 30 DAYS FOLLOWING THE COMPLETION OF ALL GRADING OPERATIONS OR USE OF HEAVY EQUIPMENT ON, OR ADJACENT TO THE SEWER, WHICH MAY CAUSE DAMAGE TO THE SEWER. THE TESTING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE PERFORMED UNDER THE DIRECTION OF THE ENGINEER.

ALL SANITARY SEWER MANHOLES SHALL BE VACUUM TESTED. THE TESTING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE PERFORMED UNDER THE DIRECTION OF THE ENGINEER.

ALL REINFORCED CONCRETE SANITARY SEWERS SHALL BE SUBJECTED TO AN INFILTRATION OR EXFILTRATION TEST. THE TESTING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE PERFORMED UNDER THE DIRECTION OF THE ENGINEER.

ALL SANITARY SEWERS SHALL BE TV INSPECTED NO SOONER THAN 30 DAYS FOLLOWING THE COMPLETION OF ALL GRADING OPERATIONS OR USE OF HEAVY EQUIPMENT ON, OR ADJACENT TO THE SEWER, WHICH MAY CAUSE DAMAGE TO THE SEWER. PRIOR TO THE TV INSPECTION ALL SEWERS SHALL BE JET FLUSHED. A SUITABLE AMOUNT OF WATER SHALL BE PUT INTO THE SYSTEM SUCH THAT ALL SAGS SHALL BE NOTICEABLE DURING THE INSPECTION.

THE OWNER SHALL BE RESPONSIBLE FOR THE INITIAL TV INSPECTION OF THE GRAVITY SEWERS. ALL JET FLUSHING, REINSPECTION AND CLEANING OF THE GRAVITY SEWERS DUE TO REPAIRS SHALL BE PAID FOR BY THE CONTRACTOR.

THE HYDROGTATIC TEGTING OF SANITARY FORCE MAINS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE PERFORMED UNDER THE DIRECTION OF THE ENGINEER.

THE CONTRACTOR SHALL NOTIFY THE LFUCG AND THE ENGINEER 12 HOURS PRIOR TO ANY TESTING AND TYING INTO ANY EXISTING SEWER.

#### SITE GRADING NOTES:

ALL SPOT ELEVATIONS INDICATE FINISH GRADE OF SURFACE. ADJUSTMENTS MUST BE MADE TO ESTABLISH GRADES OF SUB-BASE OR SUBGRADE.

CONTRACTOR SHALL, BEFORE STARTING SITE EXCAVATION, STRIP ALL TOPSOIL FROM PORTIONS OF THE SITE TO BE DEVELOPED AND STORE IN A LOCATION THAT WILL NOT INTERFERE WITH SITE DEVELOPMENT OPERATIONS. CONTRACTOR SHALL BE RESPONSIBLE FOR REDISTRIBUTING TOPSOIL IN FINSH GRADE AREAS, BACKFILLING CURBS, SIDEWALKS, ETC.

SHOULD CONTRACTOR ENCOUNTER ROCK EXCAVATION, THE ROCK SHALL BE REMOVED TO A MINIMUM DEPTH OF 12 INCHES BELOW SUBGRADE. REFILL SHALL BE IN ACCORDANCE WITH GEOTECHNICAL NOTES.

THE OVERLOT RE-GRADE LINES SHOWN HEREON ARE FOR DETERMINING DRAINAGE LIMITS AND EARTHWORK QUANTITIES AND ARE SUJECT TO REVISION DURING CONSTRUCTION. GENERAL DRAINAGE PATTERNS WILL BE MAINTAINED. SPECIFIC OVERLOT GRADES MAY VARY.

#### STORM SEWERS

STORM SEWERS SHALL BE REINFORCED CONCRETE PIPE OR SMOOTH WALLED CORRUGATED PLASTIC PIPE (UP TO 36" DIAMETER).

ALL PUBLIC STORM SEWERS SHALL BE VIDEO INSPECTED NO SOONER THAN 30 DAYS FOLLOWING COMPLETION OF ALL GRADING OPERATIONS OR USE OF HEAVY EQUIPMENT ON, OR ADJACENT TO THE SEWER. PRIOR TO THE TV INSPECTION THE STORM SEWER SHALL BE JET FLUSHED.

THE CONTRACTOR SHALL NOTIFY THE LFUCG AND THE ENGINEER 12 HOURS PRIOR TO ANY TESTING.

## UTILITY OWNERS:

MR.ERIC STIGALL KENTUCKY-AMERICAN WATER COMPANY 2300 RICHMOND ROAD LEXINGTON, KENTUCKY 40502 PHONE: 859-268-6359


MR. TOM WALKER CONSTRUCTION SUPERVISOR COLUMBIA GAS OF KENTUCKY 2001 MERCER ROAD LEXINGTON, KENTUCKY 40512-4241 PHONE: 859-288-0236


MR. RICHARD COMPTON HEAD OF ENGINEERING KENTUCKY UTILITIES 500 STONE ROAD LEXINGTON, KENTUCKY 40503 PHONE: 859-361-4309


MR. MARTIN MILTON MAINTENANCE SUPERVISOR SPECTRUM 2544 PALUMBO DRIVE LEXINGTON, KENTUCKY 40509 PHONE: 859-514-1439


INS. LEZLIE ALLISON ENGINEERING AND CONSTRUCTION MANAGER WINDSTREAM 130 WEST NEW CIRCLE ROAD SUITE 170 LEXINGTON, KENTUCKY 40505 PHONE: 357-6205


MR. JUD SMITH METRONET 601 BIZZEL DRIVE LEXINGTON, KY 40510 PHONE: 859-185-0262
















#### Wetland Planting Plan

The wetland creation areas are comprised of four main habitats based on average water depth:

• Open Water – 18 to 36 inches deep

- Deep Marsh 12 to 18 inches deep Shallow Marsh – 6 to 12 inches deep
- Sedge Meadow 0 to 6 inches deep

Species lists for each habitat zone are provided below along with proposed seeding and plug planting specifications.

ZONE 1 – OPEN WATER

#### PLUG PLANTING LIST

COMMON NAME	SCIENTIFIC NAME	
Water Shield	Brasenia schreberi	
American Lotus	Nelumbo lutea	
Yellow Pond Lily	Nuphar advena	
Yellow Pond Lily	Nuphar lutea	
American White Water Lily	Nymphaea odorata	

Notes: 5-foot spacing (1,750/acre)

Plant minimum of 3 species, of which no one species to compromise greater than 40% of total. Equivalent native species may be substituted based on availability.

SHALLOW MARS	H WETLAND SEEDING
COMMON NAME	SCIENTIFIC NAME
Swamp Milkweed	Asclepias incarnata
Purple Stemmed Aster	Aster puniceus
Beggar Ticks	Bidens frondosa
Marsh Marigold	Caltha palustris
Bailey's Sedge	Carex baileyi
Cosmos (Bristly) Sedge	Carex comosa
Fringed (Nodding) Sedge	Carex crinita
Hop Sedge	Carex lupulina
Lurid (Shallow) Sedge	Carex lurida
Blunt Broom Sedge	Carex scoparia
Awl Sedge	Carex stipata
Bristlebract Sedge	Carex tribuloides
Tuckerman's Sedge	Carex tuckermanii
Fox Sedge	Carex vulpinoidea
Turtlehead	Chelone glabra
Joe Pye Weed	Eupatorium fistulosum
Boneset	Eupatorium perfoliatum
Rattlesnake Grass	Glyceria canadensis
Blue Flag	Iris versicolor
Soft Rush	Juncus effusus
Square Stem Monkey Flower	Mimulus ringens
Ditch Stonecrop	Penthorum sedoides
Duck Potato (Arrowhead)	Sagittaria latifolia
Hard Stemmed Bulrush	Scirpus acutus
Green Bulrush	Scirpus atrovirens
Wool Grass	Scirpus cyperinus
Many Leaved Bulrush	Scirpus polyphyllus
Soft Stem Bulrush	Scirpus validus
Rough Leaved Goldenrod	Solidago patula
Eastern Bur Reed	Sparangium americanum
Giant Bur Reed	Sparangium eurycarpum
Blue Vervain	Verbena hastata

5

PLUG
COMMON NAME
American Water-plantain
Turtlehead
Common Spikerush
Blue Flag Iris
Wingleaf Primrose Willow
Marsh Seedbox
Arrow Arum
Arrowhead
Softstem Bulrush
Green Bulrush
Noolgrass
American Bur-reed
<b>lotes:</b> 2-foot spacing (10,800/acre Plant minimum of 8 species greater than 25%. Equivalent native species m

Redtop	Agrostis gigantea
Swamp Milkweed	Asclepias incarnata
Bearded Beggarstick	Bidens aristosa
Devil's Beggartick	Bidens frondosa
Fringed Sedge	Carex crinita
Frank's Sedge	Carex frankii
Short's Sedge	Carex shortiana
Fox Sedge	Carex vulpinoidea
Joe Pye Weed	Eupatorium fistulosum
Common Boneset	Eupatorium perfoliatum
Fowl Mannagrass	Glyceria striata
Fall Sneezeweed	Helenium autumnale
Slimpod Rush	Juncus diffusissimus
Soft Rush	Juncus effusus
Torrey's Rush	Juncus torreyi
Great Blue Lobelia	Lobelia siphilitica
Peppermint	Mentha x piperita
Monkey Flower	Mimulus ringens
Florida Paspalum	Paspalum floridanum
Field Paspalum	Paspalum laeve
Shortbristle Horned Beaksedge	Rhynchospora cornicu
Clustered Beaksedge	Rhynchospora glomera
Canadian Burnett	Sanguisorba canadens
Rough Leaved Goldenrod	Solidago patula
Prairie Cordgrass	Spartina pectinata
Swamp Vervain	Verbena hastata
Ironweed	Vernonia noveboracen

#### UG PLANTING LIST

SCIENTIFIC NAME
Alisma subcordatum
Chelone glabra
Eleocharis palustris
 Iris virginica
Ludwigia decurrens
Ludwigia palustris
Peltandra virginica
 Sagittaria latifolia
 Schoenoplectus tabernaemontani
Scirpus atrovirens
Scirpus cyperinus
Sparganium americanum

s, of which no one species to comprise may be substituted based on availability.

#### DEEP MARSH WETLAND SEEDING LIST

COMMON NAME	SCIENTIFIC NAME								
Swamp Milkweed	Asclepias incarnata								
Purple Stemmed Aster	Aster puniceus								
Beggar Ticks	Bidens frondosa								
Marsh Marigold	Caltha palustris								
Bailey's Sedge	Carex baileyi								
Cosmos (Bristly) Sedge	Carex comosa								
Fringed (Nodding) Sedge	Carex crinita								
Hop Sedge	Carex lupulina								
Lurid (Shallow) Sedge	Carex lurida								
Blunt Broom Sedge	Carex scoparia								
Awl Sedge	Carex stipata								
Bristlebract Sedge	Carex tribuloides								
Tuckerman's Sedge	Carex tuckermanii								
Fox Sedge	Carex vulpinoidea								
Turtlehead	Chelone glabra								
Joe Pye Weed	Eupatorium fistulosum								
Boneset	Eupatorium perfoliatum								
Rattlesnake Grass	Glyceria canadensis								
Blue Flag	Iris versicolor								
Soft Rush	Juncus effusus								
Square Stem Monkey Flower	Mimulus ringens								
Ditch Stonecrop	Penthorum sedoides								
Duck Potato (Arrowhead)	Sagittaria latifolia								
Hard Stemmed Bulrush	Scirpus acutus								
Green Bulrush	Scirpus atrovirens								
Wool Grass	Scirpus cyperinus								
Many Leaved Bulrush	Scirpus polyphyllus								
Soft Stem Bulrush	Scirpus validus								
Rough Leaved Goldenrod	Solidago patula								
Eastern Bur Reed	Sparangium americanum								
Giant Bur Reed	Sparangium eurycarpum								
Blue Vervain	Verbena hastata								

Notes: Seed wetland mix at 40 lbs/acre Seed minimum of 10 species on above list, of which no one species

to comprise greater than 20% Seed annual cover (oats) at 50 lbs/acre, as needed Equivalent native species may be substituted based on availability.

wamp MilkweedAsclepias incarnataew England AsterAster novae-angliaeeurple Stemmed AsterAster puniceuslat Topped White AsterAster umbellatusodding Bur MarigoldBidens cernuadild Brome GrassBromus altissimusosmos (Bristly) SedgeCarex comosaop SedgeCarex lupulinaurid (Shallow) SedgeCarex scopariawi SedgeCarex stipataristlebract SedgeCarex tribuloidesox SedgeCarex vulpinoidea/ood ReedgrassCinna arundinaceairiginia Wild RyeElymus virginicuspotted Joe Pye WeedEupatorium fistulosumpotted Joe Pye WeedEupatorium graminifoliaough AvensGeum laciniatumattlesnake GrassGlyceria grandisommon SneezeweedHelinium autumnaleix Eye SunflowerHeliopsis helianthoidesoft RushJuncus tenuisquare Stemmed Monkey FlowerMimulus ringensitch StonecropPenthorum sedoidesireen BulrushScirpus atrovirens/ool GrassScirpus polyphyllus/ue VervainVerbena hastata	
	SCIENTIFIC NAME
Swamp Milkweed	
New England Aster	Aster novae-angliaee
Purple Stemmed Aster	Aster puniceus
Flat Topped White Aster	Aster umbellatus
Nodding Bur Marigold	Bidens cernua
Wild Brome Grass	Bromus altissimus
Cosmos (Bristly) Sedge	Carex comosa
Hop Sedge	Carex lupulina
Lurid (Shallow) Sedge	Carex Iurida
Blunt Broom Sedge	Carex scoparia
Awl Sedge	Carex stipata
Bristlebract Sedge	Carex tribuloides
Fox Sedge	Carex vulpinoidea
Wood Reedgrass	Cinna arundinacea
Virginia Wild Rye	Elymus virginicus
Joe Pye Weed	Eupatorium fistulosum
Spotted Joe Pye Weed	Eupatorium maculatum
Boneset	Eupatorium perfoliatum
Grass Leaved Goldenrod	Euthamia graminifolia
Rough Avens	Geum laciniatum
Rattlesnake Grass	Glyceria candensis
American Mannagrass	Glyceria grandis
Common Sneezeweed	Helinium autumnale
Ox Eye Sunflower	Heliopsis helianthoides
Soft Rush	Juncus effusus
Path Rush	Juncus tenuis
Square Stemmed Monkey Flower	Mimulus ringens
Ditch Stonecrop	Penthorum sedoides
Green Bulrush	Scirpus atrovirens
Wool Grass	Scirpus cyperinus
Many Leaved Bulrush	Scirpus polyphyllus
Blue Vervain	Verbena hastata
Giant Ironweed	Vernonia gigantea
Golden Alexanders	Zizia aurea

Notes:

Seed sedge meadow mix at 40 lbs/acre Seed minimum of 10 species on above list, of which no one species to comprise greater than 20% Seed annual cover (oats) at 50 lbs/acre, as needed.

Equivalent native species may be substituted based on availability.

7

#### ZONE 3 - SHALLOW MARSH

#### PLUG PLANTING LIST

COMMON NAME	SCIENTIFIC NAME
Marsh Marigold	Caltha palustris
Fringed Sedge	Carex crinita
Frank's Sedge	Carex frankii
Short's Sedge	Carex shortiana
Fox Sedge	Carex vulpinoidea
Blunt Spikerush	Eleocharis obtusa
Common Spikerush	Eleocharis palustris
Halberdleaf Rosemallow	Hibiscus laevis
Virginia Iris	Iris virginica
Rice Cutgrass	Leersia oryzoides
Whitegrass	Leersia virginica
Cardinal Flower	Lobelia cardinalis
Curlytop Knotweed	Polygonum lapathifolium
Pennsylvania Smartweed	Polygonum pensylvanicum
Pickerelweed	Pontederia cordata
Broadleaf Arrowhead	Sagittaria latifolia
Lizard's Tail	Saururus cernuus
Softstem Bulrush	Schoenoplectus tabernaemontani
Green Bulrush	Scirpus atrovirens
American Burreed	Sparganium americanum
Giant Burreed	Sparganium eurvcarpum

#### Notes:

2-foot spacing (10,800/acre) Plant minimum of 10 species, of which no one species to compromise greater than 25%. Plant minimum of 10 species, of which no one species to comprise greater than 25%. Equivalent native species can be substituted based on availability.

#### Seeding Specifications


- 1. Seeding shall be accomplished between October 1 and July 15, unless otherwise approved by the engineer.
- 2. Seed oats (an annual cover species) should be added to all seed mixes at a rate of 50 Ibs/acre for any bare exposed soil. Any substitutions from the approved list must be approved by the engineer.
- 3. The areas should be drained to reduce standing water, to the extent practical, and seed should be sown via the broadcast method. The deep marsh and shrub swamp habitats, or other areas with muddy surface conditions, should not be ground prepped or mulched. In the shallow marsh and sedge meadow, non-saturated surface areas should be tilled/disked to a depth of 2 inches prior to seeding, and clean straw mulch should be applied at a rate of 2 tons per acre immediately following seeding. Mulched areas shall be crimped to stabilize straw on the surface.
- Allow the deep marsh and shrub swamp habitats to retain water at depths no greater than three inches for one month following seeding.
- 5. Water all seeded areas weekly for up to two months after seeding, if dry conditions persist.


#### Plug Planting Specifications


- 1. Planting of live wetland plugs should be accomplished between April 15 and September 15, unless otherwise approved by the engineer.
- Plugs shall be a minimum of 2.5 inches diameter by 3 inches deep, well-rooted through the container, and shall be inoculated with mycorrhizal fungi.
- 3. Any substitutions from the approved list must be approved by the engineer.
- 4. Plugs shall be planted in pods of 20 plants consisting of two to four species in the specified densities within the open water, deep marsh, shallow marsh, and sedge meadow habitats.
- Plugs shall be planted by excavating holes with hand tools, placing the plugs level with existing ground surface, and backfilling and firming soil around plug.
- 6. Thoroughly saturate the soil in the planted area to a depth of four inches immediately after planting plugs.
- 7. Maintain a minimum water depth of 2 to 12 in the open water area for one month after planting and then allow to fill completely.


8


8. Water planted areas weekly for up to two months after planting, if dry conditions persist.














IF ROCK IS ENCOUNTERED DURING STREET CONSTRUCTION, ADDITIONAL SUBGRADE DRAINAGE SHALL BE REQUIRED AS DIRECTED BY THE ENGINEER.

INSTALL ASPHALT WEDGING ADJACENT TO CURB INLETS ON UPSTREAM SIDE TO DIRECT RUNOFF TO GUTTERS DURING THE PERIOD OF TIME THAT FINAL SURFACE COURSE HAS NOT BEEN INSTALLED.

SCALE: |" = 50' HOR|Z. |" = 5' VERT.








LINE FF




1025


PROF NOTES: THE NOTES SHOWN BELOW SHALL APPLY TO ALL STORM SEWERS, REGARDLESS IF NOTES ARE SHOWN ON STORM PROFILE SHEET OR NOT. 1020 ALL CATCH BASIN TOP PHASES FOR GRADE BOXES SHALL BE SLOPED AT THE CURB GRADE.  $\mathbf{C}$ SEWE ALL SURFACE INLETS SHALL HAVE NO APRON UNLESS OTHERWISE NOTED. THE RIM ELEVATIONS OF ALL MANHOLES LOCATED BEHIND THE SIDEWALK SHALL BE A MAXIMUM OF 6" ABOVE THE TOP OF CURB. RM ALL TYPE A & B CURB BOX INLETS SHALL HAVE A 10 FOOT THROAT UNLESS OTHERWISE NOTED. REFER TO TO LFUCG STANDARD DRAWING NO. 211 FOR BASE REINFORCEMENT FOR MANHOLES DEEPER THAN 0 PROVIDE 6" FLEXIBLE PERFORATED PIPE WITH FOR SUBGRADE DRAINAGE 100 FEET EACH WAY FROM SAG BASINS AND 100 FEET UPHILL OF BASINS ON GRADE. ဟ STORM SEWERS SHALL BE REINFORCED CONCRETE PIPE OR SMOOTH WALLED CORRUGATED PLASTIC PIPE (UP TO 36" DIAMETER). CORRUGATED PLASTIC PIPE (CPP) SHALL NOT BE USED WHEN SEWER DEPTHS EXCEED 15-FT. CPP SHALL MEET SPECIFICATIONS AS DETAILED IN LFUCG STORWATER MANUAL, SECTION 6.4. 1000 REINFORCED CONCRIETE PIPE SHALL HAVE A MINIMUM OF 18" OF COVER. CORRUGATED PLASTIC PIPE SHALL HAVE A MINIMUM OF 24" OF COVER. ALL PUBLIC STORM SEWERS SHALL BE VIDEO INSPECTED NO SOONER THAN 30 DAYS FOLLOWING COMPLETION OF ALL GRADING OPERATIONS OR USE OF HEAVY EQUIPMENT ON, OR ADJACENT TO THE SEWER. PRIOR TO THE TV INSPECTION OF THE STORM SEWER SHALL BE JET FLUSHED. CONTRACTOR TO VERIFY 18" SEPARATION BETWEEN STORM AND SANITARY SEWER PIPE CROSSINGS. IN CASES WHERE THE SEPARATION IS LESS THAN 18", CONCRETE CRADLE SHALL BE INSTALLED PER THE SEWER CROSSING DETAIL. THE CONTRACTOR SHALL NOTIFY THE LFUCG AND THE ENGINEER 12 HOURS PRIOR TO ANY TESTING. CONTRACTOR TO VERIFY LOCATION, ELEVATION AND MATERIAL TYPE OF ALL STRUCTURES AND PIPES PRIOR TO CONSTRUCTION. STRUCTURES GREATER THAN 4-FT IN HEIGHT SHALL HAVE STEPS INSTALLED PER LFUCG STANDARDS. PRECAST SUPPLIER TO REVIEW DESIGN OF DBI'S FOR DEPTHS GREATER THAN & FEET AND MH'S AND CB'S FOR DEPTHS GREATER THAN IO FEET AND MODIFY IF NECESSARY. ALL INLETS DRAING TO INFILATRATION BASINS SHALL BE CONSTRUCTED WITH ADS FLEXSTORM STAINLESS STEEL FTC INLET FILTERS, OR EQUAL. SCALE: |" = 50' HORIZ.


1" = 5' VERT.














LINE PP







NOTES:

OF CURB.

DIAMETER).

24" OF COVER.

INSTALLED PER LFUCG STANDARDS.

INLET FILTERS, OR EQUAL.

PROFILE SHEET OR NOT.

# A. SITE DESCRIPTION

The project know as Andover Club 3450 &, 3550 Todds Road is a 4 acre Commercial development located in southeast Fayette County, on a portion of the Andover Golf and Country Club. The property currently is mixture of parking lot and golf course. Runoff from the site will be collected in storm sewers and discharged into a proposed Stormwater Management Facility located within the project . All storm sewers shall be protected with modified silt checks and the outlet is protected with a large stone silt check. All erosion control features shall remain in place until 70% of the upstream development is re-vegetated.

#### **B. SEDIMENT AND EROSION CONTROL MEASURES**

1) Prior to moblization, all tree protection fence and silt fence shall be installed.

2) Silt fences shall comply with figure 11-21 & 11-22 in the Stormwater Manual.

3) The construction entrance(s) shall be constructed during the first phases of the mobilization.

4) Phase II silt fence shall be placed behind the curb following the completion of the paving operations.

5) The stone silt check below the existing pond and above the proposed wetland shall be installed prior to clearing and grubbing.

6) At the completion of the downstream segments of storm sewers discharging into the storm water management facilities, the stone silt checks shall be installed.

7) The infiltration basins shall be installed with the paving operations. The storm sewers shall be cleaned prior to installation of the basins.

8) The wetlands and storm water management facility shall be shaped during the initial grading operations and shall serve as silt control throughout the project.

9) The wetlands and storm water management facility shall be cleaned out when  $\frac{1}{3}$  of the volume is lost. All silt shall be removed and a minimum of one foot of topsoil shall be spread in the bottom of the wetlands prior to seeding and/or planting.

10) All materials resulting from the clearing and grubbing operations shall be disposed of by the contractor. The material shall not be buried within the lots, right-of-ways or designated greenways. Burning pits shall be located as directed by the Engineer and approved by the Fire Marshall.

11) Additional erosion control measures, in addition to those shown on the plans, may be required. The measures may include seeding, mulching, silt fence, straw bales, stone silt checks, and armoring of silt fence as necessary to prevent soil erosion.

12) The existing vegetation shall be preserved where possible.

13) All disturbed areas shall be stabilized. Permanent stabilization shall begin within 14 days of completion of activities. Temporary stabilization shall be provided in any portion of the site that remains inactive for more than 21 days. Stabilization practices shall include seeding, mulching, placing sod, planting trees or shrubs, and using geotextile fabrics and other appropriate measures.

14) Following construction slopes steeper than 5:1 located outside the house contruction footprint shall be seeded and protected with erosion control blanket or netting.

15) If grading occurs during the winter months, the use of winter wheat or other recommended seed should be considered. When seasonal conditions prohibit the application of temporary or permanent seeding, non-vegetative soil stabilization practices such as mulching and netting shall be used until such times as conditions permit.

16) The performance of the erosion control plan shall be monitored weekly and following each significant rainfall in excess of 1/2". The silt control devices are to be inspected, cleaned, and repaired, if necessary.

17) All erosion control features shall be cleaned and maintained so that they remain functional throughout the project.

18) The basins shall be kept clean of debris and trash throughout the project.

19) Silt fence shall be cleaned out/repaired when silt buildup reaches 1/3 of the fence height.

20) All storm inlets shall be protected from sediment using the modified silt check as shown on the plans.

22) Upon completion of the final grading operations all surface inlets shall be protected by the modified silt checks as shown on the plans.

23) All sediment control features shall remain in place until the site has been re-vegetated and the ultimate water quality features are in place and accepted by the Engineer.

system.

## D. OTHER CONTROL MEASURES

2) Sediment from vehicles tracking onto pavement and from dust generated onsite shall be minimized. All mud tracked onto adjoining roadways shall be cleaned immediately.

3) Sanitary and waste disposal shall comply with the project specifications, or applicable state or local regulations.

#### F. MAINTENANCE

#### G. INSPECTION

2) The inspections shall be performed by qualified representatives of the Engineer or the Developer.

3) The findings of the inspections shall be hand delivered or faxed to the Contractor or Developer.

5) Control measures shall be inspected to ensure correct operation. Accessible discharge locations shall be inspected to insure that velocity dissipation devices are effective in preventing significant impacts to receiving waters.

6) Disturbed areas and material storage areas that are exposed to precipitation shall be inspected for evidence of, or the potential for, pollutants entering the drainage system.

8) The inspection reports shall be provided to the Engineer for incorporation into the Best Management Practices Plan.

21) Topsoil stockpiles and borrow sites shall be surrounded by silt fences, re-seeded, and placed where soil erosion will not go into the sediment basins.

## C. Storm Water Management Devices

1) All storm water runoff leaving the paved portions of the site shall be collected in the storm sewer

2) The discharge from this development shall be controlled by a storm water management facility and wetland basin located within the project. Sediment shall be controlled with diversion ditches, silt fence and silt checks. The above structures shall be maintained throughout the construction process.

1) No solids, including building materials, shall be allowed to discharge into waters of the Commonwealth.

4) An area shall be designated for employee parking and storage of materials. The area shall be maintained throughout the project and , if necessary, be covered with stone to prevent erosion.

#### E. OTHER STATE OR LOCAL PLANS

1) All work shall be performed in accordance with the Lexington-Fayette Urban County Government's requirements with respect to storm water management and erosion control.

2) All work within the existing streams and wetlands shall be performed in accordance with the Corp of Engineers Permit and the Water Quality Certification issued by the Kentucky Division of Water.

Refer to Section B for discussion of maintenance of the sediment control features.

1) Refer to Section B for discussion of inspections of the sediment control features.

4) Revisions to the Best Management Practices Plan based on the results of an inspection shall be implemented within (7) seven days.

7) Reports of the inspections including the scope, names and qualifications of personnel of persons making the inspection, the date of the inspection, major observations relating to the implementation of the Best Management Practices Plan, and any corrective actions taken shall be made and kept for a period of three (3) years or until one (1) year after the permit ends.

#### H. NON-STORM WATER DISCHARGES

1) The site shall be maintained in a manner such that non-storm water discharges including leakages/spills (i.e. Hydraulic Fluid, Antifreeze, Brake Fluid, Oils, etc.) are prevented from entering the retention basin or ultimately leaving the site.

2) Should a non-stormwater discharge occur the proper authorities shall be notified (Division of Environmental Services and Division of Water.

3) The only non-storm water discharges which are permitted are those from fire fighting activities, fire hydrant flushing, potable water sources, water line flushing, irrigation or lawn watering, detergent free building or pavement washing where spills or leaks of toxic materials have not yet occurred or have been completely removed, air conditioning condensation, natural springs, and uncontaminated ground water sources.

#### I. CONTRACTORS AND SUBCONTRACTORS

1) The general contractor or developer shall furnish the Engineer with the contractor or subcontractor that is responsible for implementing and maintaining each portion of the sediment control measures shown on the plans or outlined in this Best Management Practices Plan.

2) All contractors and subcontractors shall sign a copy of the certification statement below before conducting any professional service at the site:

"I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Discharge Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification."

Copies of the certifications shall be submitted to the Engineer for inclusion in the Best Management Practices Plan.

#### EARTHWORK SEQUENCES

1) CLEARING AND GRUBBING.

2) TOPSOIL EXCAVATION AND STOCKPILING.

3) EMBANKMENT CONSTRUCTION AND EXCAVATION.

4) HOME BUILDING AND FINAL YARD GRADING. 5) RE-VEGEATION AND LAWN ESTABLISHMENT.

CONTRACTOR / SUBCONTRACTOR CERTIFICATION

ANDOVER CLUB CLUBHOUSE LEXINGTON, FAYETTE COUNTY, KENTUCKY

NAME \_\_\_\_\_ COMPANY \_\_\_\_\_ TITLE \_\_\_\_\_ ADDRESS \_\_\_\_\_

PHONE \_\_\_\_\_

"I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Discharge Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification."

SIGNATURE

## J. BMP SEQUENCING

Install silt fence and or tree protection fence, construction entrance and silt checks.

Begin demolition, clearing and grubbing operations. Stockpile topsoil outside disturbed area.


Perform grading operations.

Construct storm sewers and sanitary sewers. Install stone silt checks at the storm sewer outlets upon completion of downstream segments.


Install catch basin inlet protection and channel lining at the storm sewer and culvert outlets. Reconstruct stone silt checks as necessary.

Install Phase II silt fence at the back of the curb. Seed and protect all disturbed areas.


dtd Partners, 40 Ŵ S  $\mathbf{O}$ NOTE ဟ Ш Ш CTIC **C** COUS ANDOVEF CLUBHO ON, FAYETTE ( EMENT MANAGE ON, BEST EXIN( ΤWΗ DRAWN DATE 06/13/23 CHECKED REVISED SHEET



# **CONSTRUCTION ENTRANCE**




# **TEMPORARY DIVERSION DITCH**





- 6. A WIRE MESH SUPPORT FENCE SHALL BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING HEAVY DUTY WIRE STAPLES AT LEAST 1 INCH IN LENGTH, WIRE TIES OR HOG RINGS. THE WIRE SHALL EXTEND INTO THE TRENCH A MINIMUM OF 2 INCHES AND SHALL NOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL
- GROUND SURFACE. 7. WASHED STONE SHALL BE USED TO BURY SKIRT WHEN SILT FENCE IS USED ADJACENT TO A CHANNEL, CREEK OR POND.
- 8. TURN SILT FENCE UP SLOPE AT ENDS.


# **TEMPORARY SILT FENCE GENERAL NOTES**














# SILT FENCE DETAIL



				10	) }	É	4R	STC	RM	DE	51G	$\mathbb{N}$									10	0	YE	AR	ST	ORM	1 C+	HEC	K				
Pipe	Start-Node	Stop-Node	Inlet A (acres)	С	TotCA (acres)		Sys Flow Time (min)	e Length (ft)	5 (ft/ft)	Shape	Size (in)	V avg (fi/s)	Q (cfs)	Cap (cís)	Up Gr. (ft)	Up HGL (ft)	Pipe	Start-Node	Stop-Node	Inlet A (acres)	С	Tot CA (acres)		Bys Flow Time (min)	Length (fi)	9 (ft/ft)	Shape	Size (in)	V avg (fi/s)	Q (cís)	Cap (cís)	Up Gr. (ft)	Up HGL (ft)
P-AA-1	MH AA-2/QQ-1	HDWL AA-I	(N/A)	(N/A)	4.09	0	12.05	134.50	0.01	Circle	24	<b>8</b> .71	20.30	24.46	1013.80	1005.24	P-AA-I	MH AA-2/QQ-1	HDWL AA-I	(N/A)	(N/A)	4.09	0	12.41	134.50	0.01	Circle	24	8.77	26.03	24.46	1013.80	1005.41
P-AA-2	СВ АА-3	MH AA-2/QQ-1	1.85	0.70	1.52	10	10.21	193.90	0.03	Circle	15	10.57	8.06	12.13	1018.08	1014.52	P-44-2	CB 44-3	MH AA-2/QQ-I	1.85	0.70	1.52	10	10.46	193.90	0.03	Circle	15	11.11	10.40	12.13	1018.08	1014.59
P-AA-3	CB AA-4	СВ АА-3	0.25	0.90	0.23	10	10.00	55.40	0.01	Circle	12	4.33	1.20	3.85	1019.00	1014.94	P-AA-3	CB AA-4	CB AA-3	0.25	0.90	0.23	10	10.00	55.40	0.01	Circle	12	/.99	1.56	3.85	1019.00	1015.26
P-EE-I	CB EE-2	MH EE-I	1.00	0.90	1.04	10	10.50	28.40	0.027	Circle	15	9.30	5.44	11.59	1014.50	1010.87	P-EE-I	CB EE-2	MH EE-I	1.00	0.90	1.04	10	10.47	28.40	0.027	Circle	15	9.9/	7.08	11.59	1014.50	1010.99
P-EE-2	CB EE-3	CB EE-2	0.15	0.90	0.14	10	10.00	162.70	0.028	Circle	12	5.40	0.72	6.40	1018.50	1014.85	P-EE-2	CB EE-3	CB EE-2	0.15	0.90	0.14	10	10.00	162.70	0.028	Circle	12	5.83	0.94	6.40	1018.50	1014.91
<i>P-FF-</i> /	CB FF-2	HDWL FF-I	0.90	0.80	0.72	10	10.00	31.10	0.035	Circle	12	9. <i>34</i>	3.85	7.22	1010.40	1005.23	P-FF-/	CB FF-2	HDWL FF-I	0.90	0.80	0.72	10	10.00	31.10	0.035	Circle	12	9.9 <i>3</i>	5.01	7.22	1010.40	1005.32

